

BIDDING AND CONTRACT DOCUMENTS  
ADDENDUM NO. 6

DATE: July 17, 2024

Hurst-Rosche, Inc.  
1101 Kermit Drive, Suite 620  
Nashville, Tennessee 37217

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 6 TO THE BIDDING DOCUMENTS FOR

Montgomery Bell State Park Four Mile Creek Campground Renovation  
Montgomery Bell State Park  
Burns, Dickson County, Tennessee  
SBC No. 126/054-01-2022

This addendum forms a part of the bidding and contract documents and modifies the bidding documents dated April 24, 2024. Acknowledge receipt of this addendum in space provided on Bid Form.

.....

RFI RESPONSES

1. There are no circuit designations for hand dryers.
  - a. **Clarification:** Circuits for equipment that are existing to remain or to be replaced in same location are not shown, only mentioned in electrical set.
  
2. How are we to handle electrical in the event of rock. Per code, we have to run THNN wire in conduit and encased in concrete. We cannot use buried cable in rock.
  - a. **Clarification:** If the contractor runs into rock, they'll have to go around it, chop it up, or bore through it. For ground rods, there are options such as a horizontal plate that could be used to avoid rock. Electrical can provide more information as needed.
  
3. Is the intention for the trees to be cut down or pushed over by equipment?
  - a. **Clarification:** The contractor may determine how trees are removed provided that tree removal maintains compliance with contract documents that specify to protect surrounding trees, utilities, structures, etc.
  
4. Please confirm that tent platform handrails only cover the front [high] side and 2 ends of the platform.
  - a. **Clarification:** Correct, the design intent is to provide railing on 3 sides and leave the edge of the platform that meets the hill slope open with no railing.
  
5. Please confirm the alternate for the tent platform is only for the deck surface going to a Trex like product.
  - a. **Clarification:** Correct, Alternate 2 is to swap out the material of the tent platforms with a more durable composite decking as well as any other indicated items such as handrails in the plan details.

- 6. Please confirm slab thickness at trash enclosure is 6".
  - a. **Clarification:** Trash enclosure slab is existing, verify in field.
- 7. Please advise if there will be a concrete apron approach at trash enclosure.
  - a. **Clarification:** No concrete apron shown in plan for trash enclosure.
- 8. Please advise if 2 gate post in center of trash enclosure was the design intent and not the single post shown.
  - a. **Clarification:** Defer to manufacturer for confirmation of product limitations and strength characteristics. Ultimately this will be evaluated during submittals.
- 9. Please confirm the passage door to trash enclosure will be Certainteed gate or steel fabbed and covered.
  - a. **Clarification:** Passage door to trash enclosure is to be the same fencing material as the rest of the trash enclosure.

This addendum **DOES NOT** alter the previously published bid due date of **July 24<sup>th</sup>, 2024, 02:00 pm, at Central Procurement Office, located at William R. Snodgrass Tennessee Tower, 3<sup>rd</sup> Floor, Nashville, TN 37243-1102.**

Respectfully submitted,

HURST-ROSCHE, INC.

Alex Grenhoff  
Project Manager



07/17/2024

DATE

03/31/2025

LICENSE EXPIRES

ADDENDUM NO. 6 RECEIVED BY:

\_\_\_\_\_  
Authorized Representative

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Date