

DATE: 02-26-2020

HURST-ROSCHE, INC.
1400 E. Tremont Street
Hillsboro, Illinois 62049
217-532-3959

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 1 TO THE BIDDING DOCUMENTS FOR

Calhoun High School Door Replacement
Calhoun Unit District 40
Hardin, Calhoun County, Illinois
HR # 270-2896

This addendum forms a part of the bidding and contract documents and modifies the original bidding documents dated February 17, 2020. Acknowledge receipt of this addendum in the space provided on the Bid Form. **FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

Upon receipt of this addendum, please sign below and email to Hurst-Rosche, Inc. at tdownen@hurst-rosche.com within 24 hours of receipt.

RECEIVED BY:	_____
	Company Name/Authorized Representative
DATE:	_____

DRAWINGS

- A. SHEET A-101
1. **ADD** the following Remark to Door A, “REPAIR DENTED HOLLOW METAL DOOR FRAME NEAR LATCH OF DOOR PRIOR TO PAINTING FRAME. REMOVE EXISTING PAINT, APPLY AUTO BODY FILLER TO THE DENTED AREA, ALLOW TO CURE PER MANUFACTURERS INSTRUCTIONS, SAND FILLER SMOOTH.”
 2. **DELETE** “2” from Frame Elevation column of Base Bid Door Schedule for Door Z2 and **REPLACE** it with, “7 (sim.)”. **ADD** the following Remark, “TRANSOM IS SOLID PANEL TO BE PREPED, PRIMED AND PAINTED.”
 3. **DELETE** “2” from Frame Elevation column of Alternate Bid #1 Door Schedule dor Doors B, C and G and **REPLACE** it with, “7”.
 4. **ADD** “4” to the Frame Elevation column of Alternate Bid #2 Door Schedule for Door Z5.
 5. **DELETE** Keyed Note symbol #10 from Door 23 in Partial Floor Plan 1/A-101.”

This addendum consists of 2 pages and 1 attachment consisting of 1 additional page.

A. SHEET A-102

1. **DELETE** Alternate Bid #3 Door Schedule and **REPLACE** it with Attachment #1.

This addendum **DOES NOT** alter the previously published bid date of **March 10, 2020, 2:00 PM**, prevailing time, at **Calhoun Unit District 40 Unit Office, 101 Calhoun Avenue, Hardin IL**.

Sincerely,

HURST-ROSCHE, INC.

A handwritten signature in blue ink, appearing to be 'T. Downen', with a long horizontal stroke extending to the right.

Timothy L. Downen, AIA, LEED AP
cc: All plan holders

This addendum consists of 2 pages and 1 attachment consisting of 1 additional page.

ALTERNATE BID #3 DOOR SCHEDULE

DOOR No.	SIZE	SIZE	SIZE	DOOR			FRAME			Label	Re.
	Width	Height	Thick	Mat.	Finish	Elev.	Mat.	Finish	Elev.		
1	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	1
1A	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	1
1B	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	1
2	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	1
2A	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	1
3	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	2
4	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	4	--	NO SECURITY FILM, 3
4A	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	--
4B	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	2
5	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	3
8	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	3	--	NO SECURITY FILM, 1
8A	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	3
10	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	2
11	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	2
14	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	--
16A	--	--	--	--	--	--	EXGHM	P	7	--	2
17A	--	--	--	--	--	--	EXGHM	P	7	--	2
18A	--	--	--	--	--	--	EXGHM	P	7	--	2
19A	--	--	--	--	--	--	EXGHM	P	7	--	2
19B	--	--	--	EXGHM	P	B	EXGHM	P	5	--	--
23	36"+/-	96"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
A1	--	--	--	--	--	--	EXGHM	P	1	--	NO SECURITY FILM, 1
A3	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
D	--	--	--	--	--	--	EXGHM	P	2	--	--
E1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	1	--	1
K1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
L1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
M1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
N1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
Q1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
R1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
S1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
S2	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
T1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2
T2	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
U	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	9	--	3
U6	--	--	--	--	--	--	EXGHM	P	7	--	2
U7	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	7	--	2
U9	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	5	--	--
U10	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
V1	--	--	--	--	--	--	EXGHM	P	7	--	3
V2	--	--	--	--	--	--	EXGHM	P	9	--	3
V3	--	--	--	--	--	--	EXGHM	P	9	--	3
W6	--	--	--	--	--	--	EXGHM	P	7	--	2
Y1	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	5	--	--
Y2	(2)36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	5	--	--
Y3	36"+/-	84"+/-	1-3/4"	EXGHM	P	D	EXGHM	P	2	--	--
Z	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	4	--	NO SECURITY FILM, 2
Z1	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	2	--	--
Z6	36"+/-	84"+/-	1-3/4"	EXGHM	P	B	EXGHM	P	7	--	2

DOOR SCHEDULE ABBREVIATIONS:

EXGHM - EXISTING HOLLOW METAL
 HM - HOLLOW METAL
 PF - PRE-FINISHED
 P - PAINT
 WD - WOOD

DOOR SCHEDULE GENERAL NOTES:

1. SEE SPEC SECTION 08 14 16 FOR INFORMATION ON FLUSH WOOD DOORS.
2. SEE SPEC SECTION 08 71 00 FOR INFORMATION ON DOOR HARDWARE.
3. SEE SPEC SECTION 09 90 00 FOR INFORMATION ON PAINT.
4. SEE A-103 FOR DOOR AND DOOR FRAME ELEVATIONS.

REMARKS:

1. SIDELIGHTS AND/OR TRANSOMS ARE A MIXTURE OF EXISTING GLASS (NO WORK) AND EXISTING SOLID PANELS (PREP, PRIME & PAINT)
2. SIDELIGHTS AND/OR TRANSOMS ARE EXISTING SOLID PANELS (PREP, PRIME & PAINT)
3. SIDELIGHTS AND/OR TRANSOMS ARE EXISTING GLASS (NO WORK) (PREP, PRIME & PAINT)

ADDENDUM #1, ATTACHMENT #1