

DATE: December 18, 2024

HURST-ROSCHE, INC.
No. 5 Bank Square
East St. Louis, Illinois 62203
Phone: 618.398.0890

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 1 TO THE BIDDING DOCUMENTS FOR

SANITARY SEWER SYSTEM REHABILITATION, LAURALEE DRIVE & RENOIS LANE
CAHOKIA HEIGHTS
HR 860-1434

This addendum forms a part of the bidding and contract documents and modifies the original bidding documents dated December, 2024. Acknowledge receipt of this addendum in the space provided on the Bid Form. **FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

Upon receipt of this addendum, please sign below and email to Hurst-Rosche, Inc. at tsudholt@hurst-rosche.com within 24 hours of receipt.

RECEIVED BY:	_____
	Company Name/Authorized Representative
DATE:	_____

Lauralee Drive & Renois Lane

Advertisement for Bids, Bid Form, Specification Section 01010-Summary of Work and General Note 1 on Drawing Sheet 1.

CIPP lining is no longer required for this project.

Delete "and approximately 200 lineal feet of cured in place (CIPP) liner."

CLARIFICATIONS

1. The Minority Business Enterprise (MBE) goal for this project is seventeen percent (17%) of the awarded amount.
2. An Undefined Contract Action (UCA) commitment letter must be submitted with the Contractors bid regarding obligation of ARPA funds for the project. Copies were provided to the bidders at the 12/18/24 pre-bid meeting.
3. Any necessary clearing required to complete the work shall be incidental to the Cost of Construction.
4. Bypassing of existing sewer flows is the responsibility of the contractor. Existing bypass piping provided by the Owner may remain in place.
5. The new 4" diameter force main from the Renois Lane Lift Station is approximately 1,550 lineal feet in length.
6. The existing 10" diameter sewer between Manholes 8 and 9 at the Lauralee and Violet Lift Station shall be removed and replaced in its entirety. The length shown on the project drawings is approximate. Manhole 8 shall remain in place.

This addendum consists of 2 pages.


Sanitary Sewer System Rehabilitation, Lauralee Drive & Renois Lane
Cahokia Heights
December 18, 2024
Addendum No. 1

7. The existing 6" diameter force main from the No. 9 Violet Lift Station to wetwell No. 26 at the Lauralee and Violet Lift Station shall remain as shown on the project drawings.
8. The existing water lines in the vicinity of the new Renois Lane Lift Station shall remain in service and be protected by the contractor as necessary.
9. Surface water in the vicinity of the new Renois Lane Lift Station currently drains to an open field south of the project site. No. changes are anticipated to this drainage pattern.
10. The existing 8" diameter force main from the Lauralee and Violet Lift Station shall be removed and replaced as necessary.

This addendum **DOES NOT** alter the bid date of **Monday, December 23, 2024, 10:00 am** prevailing time, at Hurst-Rosche, Inc., 5 Bank Square, East St. Louis, Illinois 62203.

Respectfully submitted,

HURST-ROSCHE, INC.



Terry A. Sudholt, PE

TAS/jc
Attachment

C: All Plan Holders

This addendum consists of 2 pages.