DATE: January 11, 2022

HURST-ROSCHE, INC.
1400 E. Tremont Street
Hillsboro, Illinois 62049
217-532-3959

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 1 TO THE BIDDING DOCUMENTS FOR

GYMNASIUM HVAC REPLACEMENT
SANDOVAL HIGH SCHOOL
SANDOVAL C.U.S.D. NO. 501
SANDOVAL, MARION COUNTY, ILLINOIS
HR # 150-2081

This addendum forms a part of the bidding and contract documents and modifies the original bidding documents dated December 21, 2021. Acknowledge receipt of this addendum in the space provided on the Bid Form. **FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

****

Upon receipt of this addendum, please sign below and email to Hurst-Rosche, Inc. at tdownen@hurst-rosche.com within 24 hours of receipt.

RECEIVED BY: _____
Company Name/Authorized Representative

DATE: _____

SPECIFICATIONS

A. Section 23 76 16.13 Packaged Large Capacity Rooftop Units
   1. **DELETE** Paragraph 2.2.F.1 and **REPLACE** it with, "Voltage: 208V."
   2. **DELETE** Paragraph 2.2.F.4 and **REPLACE** it with, "Full-Load Amperes: 51A."

This addendum consists of 2 pages.

B. Section 26 28 16 Enclosed Switches and Circuit Breakers
   1. **DELETE** paragraph 1.5.A.1.
   2. **DELETE** paragraph 3.4.C.
   3. **DELETE** paragraphs 3.6.A, B and C.

C. Section 28 46 21.11 Addressable Fire-Alarm Systems
   1. **DELETE** paragraph 2.3.A.1-2; 5-8; 10-11, 13-16. Retain only Honeywell International, Inc. and its subsidiaries.

DRAWINGS

A. M-101 GYMNSIUM MECHANICAL PLAN
   1. **ADD** the following as General Note #1, "CONTRACTOR SHALL PROVIDE AND INSTALL (1) THERMOSTAT AND (1) CARBON DIOXIDE SENSOR PER RTU IN THE GYMNASIUM. EQUIPMENT SHALL BE LOCATED NEAR THE NORTH DOORS BETWEEN THE GYMNASIUM AND NORTH CORRIDOR NEAR THE STAIRS DOWN TO THE LOCKER ROOM AREA. EQUIPMENT SHALL BE MOUNTED IN A LOCKABLE CLEAR POLYCARBONATE VENTED ENCLOSURE. ALL WIRING SHALL BE SURFACE MOUNTED IN CONDUIT OR WIRE MOLD. ALL CONDUIT AND / OR WIRE MOLD SHALL BE PAINTED TO MATCH ADJACENT WALL SURFACES."

B. M-102 ROOF PLAN
   2. **ADD** the following to Keyed Note #3 text, "CONTRACTOR'S OPTION TO INSTALL GAS LINE LOW ON GYM WALL, IN SIMILAR PATH AS SHOWN, THROUGHOUT COURTYARD AREA TO THE EAST OF THE GYM, TO ENSURE SECURE ATTACHMENT DIRECTLY INTO CONCRETE WALL WHERE THICKENED WALL SECTION OF EIFS DOES NOT EXIST."

C. E-101 ELECTRICAL PLAN
   1. **ADD** the following to Keyed Note #1 text, "CONTRACTOR'S OPTION TO INSTALL CONDUIT AND ELECTRICAL WIRING FROM NEW DISTRIBUTION PANEL TO THE EQUIPMENT ON ROOF TOPS. CONDUIT SHALL BE RIGID ALUMINUM AND SHALL BE SUPPORTED WITH MIFAB C-PORT PIPE SUPPORTS OR APPROVED EQUAL AT 5'-0" O.C.)."
   2. **ADD** the following to Keyed Note #2 text, "CONTACT FOR CURRENT FIRE ALARM MONITORING COMPANY IS SECURITY ALARM CORP., JOSH DICE, 618-548-5768."

This addendum **DOES NOT** alter the previously published bid date of **Friday, January 14, 2022, 2:00 PM,** prevailing time, at **Sandoval C.U.S.D. No. 501.**

Sincerely,

HURST-ROSCHE, INC.

Timothy L. Downen, AIA, LEED AP

cc: All plan holders

This addendum consists of 2 pages.