

DATE: 04-03-2020

HURST-ROSCHE, INC.
1400 E. Tremont Street
Hillsboro, Illinois 62049
217-532-3959

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 1 TO THE BIDDING DOCUMENTS FOR

DRAINAGE IMPROVEMENTS
NORTHWESTERN CUSD No. 2
MACOUPIN COUNTY, ILLINOIS
HR # 150-0430

This addendum forms a part of the bidding and contract documents and modifies the original bidding documents dated March 16, 2020. Acknowledge receipt of this addendum in the space provided on the Bid Form. **FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

Upon receipt of this addendum, please sign below and email to Hurst-Rosche, Inc. at tdownen@hurst-rosche.com within 24 hours of receipt.

RECEIVED BY:	_____
	Company Name/Authorized Representative
DATE:	_____

SPECIFICATIONS

- A. Section 41 13 Bid Form
 - 1. **DELETE** “All Cash and Contingency Allowances described in Section 01 20 00 - Price and Payment Procedures are included in the Bid Sum.” From paragraph 1.
- B. 01 20 00 Price and Payment Procedures
 - 1. **DELETE** Paragraph 1.1.A in its entirety.
 - 2. **DELETE** Paragraph 1.2 in its entirety.
- C. 33 42 00 Stormwater Conveyance
 - 1. **DELETE** The following portion of paragraph 3.3. “Use cast-iron soil pipe fittings in sewer pipes at branches for cleanouts and cast-iron soil pipe for riser extensions to cleanouts.”

This addendum consists of 2 pages.

DRAWINGS

A. Sheet C1.0

1. **DELETE** Note #4 and **REPLACE** it with, "The 4" diameter cast iron portions of the 8 downspouts in the west courtyard will be removed and the downspout extended in-kind to connect with the proposed boot."
2. **ADD** Note #9 as follows, "Install *Agri Drain Rat Guard* or equivalent at each tile discharge."
3. **ADD** Note #10 as follows, "Contractor to locate tile piping according to the plan dimensions and the below coordinates. The coordinates and dimensions are considered approximate. The contractor should locate to avoid conflicts with existing elements."

East Tile

Start – N1012449.42, E2345565.21

Bend – N1012176.80, E2345638.89

Bend – N1012199.55, E2345734.17

Discharge - N1012072.77, E2345768.86

West Tile

Start – N1012171.36, E2345568.58

Bend – N1012128.07, E2345426.42

Discharge - N1011969.81, E2345426.42"

B. Sheet C1.1

1. **ADD** Approximately 10' of sidewalk replacement at the south end of the Elementary School replacement. This portion angles back toward the west and should be a transition from the newly installed sidewalk back to the existing which continues to the east.

C. Sheet C2.0

1. **MODIFY** Callout on Detail 1-Proposed to be "Existing 5x4 inch downspout and metal shield (modify to receive boot)".
2. **MODIFY** Callout on Section A-A to be "6x1/4 inch galvanized steel plate, shim to be level with sidewalk."
3. **MODIFY** Callout on Section A-A to be "Galvanized 1x1x1/4 inch L (typ)"

This addendum **DOES NOT** alter the previously published bid date of **Thursday, April 9, 2020, 2:00 PM**, prevailing time, at Northwestern CUSD No. 2 located at 30953 Route 111, Palmyra, IL 62674.

Sincerely,

HURST-ROSCHE, INC.



Timothy L. Downen, AIA, LEED AP

cc: All plan holders

This addendum consists of 2 pages.