

DATE: June 10, 2022

HURST-ROSCHE, INC.
No. 5 Bank Square
East St. Louis, Illinois 62203
Phone: 618.398.0890

TO: PROSPECTIVE BIDDERS

SUBJECT: ADDENDUM NO. 1 TO THE BIDDING DOCUMENTS FOR

LIFT STATION REHABILITATION PY21
42ND STREET & MARKET AVENUE
HR 211-0482

This addendum forms a part of the bidding and contract documents and modifies the original bidding documents dated May, 2022. Acknowledge receipt of this addendum in the space provided on the Bid Form. **FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

Upon receipt of this addendum, please sign below and email to Hurst-Rosche, Inc. at tsudholt@hurst-rosche.com within 24 hours of receipt.

RECEIVED BY: _____ Company Name/Authorized Representative
DATE: _____

CLARIFICATIONS

1. I have a question on the trash debris strainer. Are you just wanting one fabricated or does it have to be by "Access Manufacturing, Inc"? I'm having trouble locating this company and it appears to possibly be out of business, thank you.

The trash strainer basket does not need to be furnished by Access Manufacturing. The trash strainer basket for a recent lift station rehab in Cahokia Heights was furnished by U.S.F. Fabrication, Inc. in Hialeah, Florida. The wetwell & valve vault access hatches for that project were also furnished by U.S.F. Fabrication. The trash strainer baskets for two current lift station rehab projects in Cahokia Heights are being furnished by Halliday Products, Inc. in Orlando, FL.

2. Are we reusing the existing conduits (2 ½" to 3", and 1" conduits) from the control panel to the wet well and valve box?

The existing conduits may be reused if they can be resealed. Otherwise, they will need to be replaced.

3. Are we replacing the 120A fused disconnect and buried conduit to the new control panel?

The 120 Amp fused disconnect is to be replaced. The existing conduit may be reused.

4. The specs make it sound like the existing service pole is being changed out, along with the entire existing service.

The existing service pole, including service to the pole, is intended to be reused.


5. The existing conduit and seals should be sealed with sealant that will not enable the seal, and any conduit and wiring that has been infiltrated with the sealant, to be reused. Do you want me to leave replacing the seals and any associated conduit out of our proposal? We could always come back with a change order later if that's how you want me to quote it.

Conduits from the control panel to the wet well need to be sealed as part of the base bid.

This addendum **DOES NOT** alter the bid date of **Thursday, June 16, 2022, 10:15 am** prevailing time, at office of Hurst-Rosche Engineers, Inc. 5 Bank Square, East St. Louis, IL.

Respectfully submitted,

HURST-ROSCHE, INC.



Terry A. Sudholt, PE

TAS/jc